

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24527-00-00
Spot: W2NENW Sec/Twnshp/Rge: 8-12S-17W
4650 feet from S Section Line, 3465 feet from E Section Line
Lease Name: SCHMEIDLER E Well #: 8
County: ELLIS Total Vertical Depth: 3710 feet

Operator License No.: 6037
Op Name: STAAB OIL CO., A GENERAL PARTNER
Address: 1607 HOPE WELL ROAD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3709	0	w/175 sxs cmt
SURF	8.625	260	0	w/150 sxs cmt

\$ 120.58

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2006 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: FRANK STAAB Company: STAAB OIL COMPANY Phone: (785) 625-5013

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV Tool at 1350' cwc w/350 sxs.
CIBP at 3590'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 210 sxs cement with 500# hulls.
S.I.P. 900#. Instant 500# on the annulus.

Perfs:

INVOICED
DATE 9/21/06
NO. 2007060572

RECEIVED
SEP 20 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

170

PKH

STAAB OIL COMPANY
HAYS, KS 67601

8-12 -17W
30'W, C E/2 W/2 NE NW

#8 SCHMEIDLER "E"

site: 6-3/4 N & 1 W OF CATHERINE, KS
contr: HELBERG OIL COMPANY
geol: LEWIS CHUBB

city: ELLIS
field: BEMIS-SHUTTS

API 15-051-24527

fr date 10/16/87 spd date 10/21/87 drlg comp 10/30/87 card issued 12/16/87 last revised 12/16/87

ELV: 2126 KB LOG	
tops.....	depth/datum
ANH.....	1340 +786
B/ANH.....	1377 +749
TOP.....	3071 -945
HEEB.....	3304 -1178
LANS.....	3345 -1219
BKC.....	3581 -1455
ARB.....	3610 -1484
LTD.....	3691 -1565
RTD.....	3710 -1584

IP status:
OIL, P 15 BO & 80 BWP, ARB 3670-3673,
CSG: 8-5/8" 260 / 150 SX, 5-1/2" 3709 / 175 SX,
MULTI-STAGE AT 1350 / 350 SX
NO CORES OR DSTS
MICT - CO, PF (ARB) 3670-3673, W / 4 SPF, AC 250
GAL, GSO, SET 2-1/2" TBG AT 3680, POP, P 15 BO & 80
BWP (GR 25), 11/16/87

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

CEP