

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24970-00-00  
Spot: S2NE Sec/Twnshp/Rge: 4-17S-14W  
1900 feet from N Section Line, 1450 feet from E Section Line  
Lease Name: CHRISTIANS Well #: 1  
County: BARTON Total Vertical Depth: 3490 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	905		

\$ 113.43

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2006 5:00 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered out 125 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: JAY PFEIFER WitnessType: NONE  
Date/Time Plugging Completed: 09/08/2006 8:15 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

1st. Plug at 3425' w/25 sxs.  
2nd. Plug at 905' w/25 sxs.  
3rd. Plug at 425' w/40 sxs.  
4th. Plug at 40' w/10 sxs - 8 5/8' wiper plug.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED  
9/21/06  
DATE  
2007060565  
WEL. NO.

RECEIVED  
SEP 20 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

(TECHNICIAN)

SEP 18 2006

PREP