

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20101-00-00
Spot: NWSENW Sec/Twnshp/Rge: 5-6S-18E
1650 feet from N Section Line, 1650 feet from W Section Line
Lease Name: 20104 JV-P HAWK Well #: 1
County: ATCHISON Total Vertical Depth: 2060 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2060	0	
SURF	8.625	626	0	

\$ 66.95

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/15/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: CEMENT FROM 2016 TO 1966, GEL FROM 1966 TO 175, CEMENT FROM 175 TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 03/15/2006 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 2016'. Pumped 38 barrels of gel and 15 sacks of cement. Had cement from 2060' to 1885' and gel from 1885' to 284'. Pulled the tubing to 284' and circulated 30 sacks of cement from 284' to surface.

Perfs:

Top	Bot	Thru	Comments
0	0		NO PERFS

RECEIVED
SEP 25 2006
KCC WICHITA

INVOICED
DATE 9/26/06
WT. NO. 2007060592

RECEIVED
KCC DISTRICT #3
SEP 22 2006 TCH
CHANUTE, KS

Remarks:
Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)