

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20102-00-00
Spot: NESESWNE Sec/Twnshp/Rge: 5-7S-21E
2188 feet from N Section Line, 1520 feet from E Section Line
Lease Name: BOLDRIDGE Well #: 1
County: ATCHISON Total Vertical Depth: 1708 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1706	0	176 SX
SURF	8.625	183	0	120 SX

\$55.51

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/10/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1665' TO 1454'. CEMENT FROM 1454' TO 1203' GEL FROM 1203' TO 175'. CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: PARTIAL
Date/Time Plugging Completed: 03/10/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1650' and pumped 14 barrels of gel. Pulled tubing to 1460' and pumped 12.5 barrels of gel and 30 sacks of cement with one sack of cottonseed hulls. Had gel from 1650' to 1460' and cement from 1460' to 1200', gel from 1200' to 275'. Pulled the tubing up to 286' and circulated 30 sacks of cement from 286' to surface.

Perfs:

Top	Bot	Thru	Comments
1402	1404		
1395	1398		
1332	1336		
1253	1255		

RECEIVED
KCC DISTRICT #3

SEP 22 2006 TCH
CHANUTE, KS

RECEIVED
SEP 25 2006
KCC WICHITA

INVOICED

DATE 9/26/06
WEL. NO. 2007060592

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

PKT