

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20186-00-00
Spot: SENWSWSE Sec/Twnshp/Rge: 14-4S-14E
810 feet from S Section Line, 2130 feet from E Section Line
Lease Name: MAUERSBERGER Well #: 15-14
County: NEMAHA Total Vertical Depth: 2675 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2659		180 SX CMT
SURF	8.625	281		135 SX CMT

\$ 86.94

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/05/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2659' TO 2557' CEMENT FROM 2557' TO 2004' GEL FROM 2004' TO 300' CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 01/09/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-05-06 ran tubing and hit bottom at 2557' and pumped 40 barrels of water and 65 sacks of cement with 1 sack of cottonseed hulls. Had cement from 2551' to 1990' and gel was placed from 1990' to 300'. Returned to the well on 1-9-06 and shot the casing off at 1105' then pulled it to 299'. Circulated 85 sacks of cement from 299' to surface and pulled the casing.

Perfs:

Top	Bot	Thru	Comments
2505	2507		
2400	2402		
2369	2371		
2310	2312		
2283	2285		
2254	2256		
2247	2249		
2203	2205		
2173	2175		
2054	2056		

RECEIVED
KCC DISTRICT #3

SEP 12 2006 TCH

CHANUTE, KS

RECEIVED

SEP 25 2006

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman
(TECHNICIAN)

INVOICED

DATE 9/26/06
INVOICE NO. 2007060592

PT