

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20187-00-00
Spot: NESW Sec/Twnshp/Rge: 14-4S-14E
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: MAUERSBERGER Well #: 11-14
County: NEMAHA Total Vertical Depth: 2786 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2762		210 SX CMT
SURF	8.625	281		130 SX CMT

\$ 90.55

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/05/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2717' TO 2498' CEMENT FROM 2498' TO 1972' GEL FROM 1972' TP 300' CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 01/07/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-5-06 ran tubing and tagged bottom at 2546'; the tubing was pulled to 2531' and loaded the hole. Pumped 40 barrels of gel and 65 sacks of cement with 1 sack of cottonseed hulls. Cement was placed from 2531' to 1962'. Moved the tubing up the hole and shot the casing off at 999.74'. Returned to the well on 1-7-06, pulled the casing up to 282' and circulated 80 sacks of cement from 282' to surface and pulled the casing.

Perfs:

Top	Bot	Thru	Comments
2446	2448		
2397	2399		
2339	2341		
2313	2315		
2284	2286		
2277	2279		
2022	2024		

RECEIVED
KCC DISTRICT #3

SEP 12 2006 TCH

CHANUTE, KS

RECEIVED

SEP 25 2006

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED

DATE

9/26/06

INV. NO.

2007060592