

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22054-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 14-27S-10W  
990 feet from N Section Line, 1050 feet from W Section Line  
Lease Name: MARY C Well #: 1-14  
County: KINGMAN Total Vertical Depth: 4458 feet

Operator License No.: 31160  
Op Name: PHILLIPS EXPLORATION COMPANY L.  
Address: 4109 IRONWOOD  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	266		

\$ 144.89

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2006 7:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO., INC. Phone: (620) 793-0840

Proposed Plugging Method: 35 sxs @ 4450'; 35 sxs @ 1500'; 35 sxs @ 1000'; 35 sxs @ 320'; 25 sxs @ 60'; 15 sxs in rathole; and 15 sxs in mousehole.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE  
Date/Time Plugging Completed: 09/09/2006 10:15 AM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The drill pipe was ran open end to 4450' and 35 sacks of cement were spotted. The drill pipe was pulled to 1500' and 35 sacks of cement was spotted. The drill pipe was pulled to 1000' and 35 sacks of cement was spotted. The drill pipe was pulled to 320' and 35 sacks of cement was spotted. The drill pipe was pulled to 60' and 25 sacks of cement was circulated to surface. The rathole was circulated with 15 sacks of cement and the mousehole was circulated with 15 sacks of cement.

Allied Cement #23849  
60/40 posmix with 4% gel

Perfs:

RECEIVED  
KCC DISTRICT #2  
SEP 13 2006  
WICHITA, KS

RECEIVED  
SEP 21 2006  
KCC WICHITA

INVOICED

DATE 9/22/06  
AMOUNT 2007060575

Remarks:

Plugged through: DP

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

PT