

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21247-00-00  
Spot: E2SESE Sec/Twnshp/Rge: 22-28S-4E  
836 feet from S Section Line, 261 feet from E Section Line  
Lease Name: MAYER Well #: 1  
County: BUTLER Total Vertical Depth: 2822 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2000		
SURF	8.625	118		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2006 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2006 6:20 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Perfs:

8/17/2006 -- Sanded back to 2772' and capped with 5 sacks of cement. Ran 1" outside 5-1/2" to 250' and circulated cement to surface. Pulled 1", ran inside 5-1/2" to 250', and circulated cement to surface.  
8/18/2006 -- Checked cement. Backside was okay. Inside 5-1/2" was down 300'.  
8/25/2006 -- Topped off with 3 yds of slurry mix.  
United #7087 -- 133 sxs  
Concrete Material Co. #400004134 -- 3 yds

**RECEIVED  
KCC DISTRICT #2  
SEP 13 2006  
WICHITA, KS**

Remarks: CONTROL # 2006-0036-001

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

**RECEIVED  
SEP 25 2006  
KCC WICHITA**

*PKT*