

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21110-01-00
Spot: N2NWNW Sec/Twnshp/Rge: 35-31S-29W
330 feet from N Section Line, 700 feet from W Section Line
Lease Name: STERN 35 Well #: 2
County: MEADE Total Vertical Depth: 7263 feet

Operator License No.: 8802
Op Name: COBRA OIL & GAS CORPORATION
Address: PO BOX 1929
WOODWARD, OK 73802

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	55		WITH 10 SX CMT
L1	4.5	6665		
PROD	7	5665	2034	WITH 305 SX CMT
SURF	9.625	1525		WITH 520 SX CMT

\$ 236.05

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/05/2006 12:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: FILL WITH HULLS & MUD TO 4750'. SPOT 40 SX CMT AT 4750'. 75 SX CMT AT 1555'. 40 SX CMT AT 550'. 12 SX CMT AT 40'.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/07/2006 12:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

4 1/2" LINER FROM 4781-6665'. 1ST PLUG PUMP 400# HULLS & 40 SX CMT
DISPLACED TO 4750' WITH MUD. 2ND PLUG AT 1555' WITH 75 SX CMT. 3RD PLUG
AT 550' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 12 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5872	5878		
5854	5860		
5772	5776		
5762	5768		
5696	5704		
5678	5684		
5667	5672		

INVOICED
DATE 9/26/06
WEL NO. 2007060589

RECEIVED


SEP 25 2006

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT.

Plugged through: CSG

District: 01



Signed

Jerry W. Stapleton
(TECHNICIAN)

PART II

PRT