

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-00517-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 35-3S-24W  
2310 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: SCHOEN A Well #: 5  
County: NORTON Total Vertical Depth: 3758 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3754	0	w/265 sxs cmt
SURF	8.625	275	0	w/125 sxs cmt

\$ 122.14

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2006 9:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 240 sxs Midcon II cement and 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/08/2006 2:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 275' w/125 sxs.  
5 1/2" production casing set at 3754' w/265 sxs.  
TD at 3758'. Dakota at 1039' - 1339'. Anhy at 2013' - 2033'.  
Casing holes at 3182' - 1796' - 1642' and above.  
Ran tubing to 3700' - pumped 100 sxs cement with 300# hulls.  
Pulled tubing to 1450' - pumped 75 sxs cement with 300# hulls - cement to surface.  
Pulled tubing to surface. Connected to 5 1/2" casing and pumped 20 sxs cement.  
Max. P.S.I. 600#. S.I.P. 300#.  
Connected to 8 5/8" surface casing and pumped 30 sxs cement.  
Max. P.S.I. 50#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3754	3758		OPEN HOLE

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Darrel Dipman  
(TECHNICIAN)

RECEIVED

SEP 25 2006

KCC WICHITA

Form CP-2/3

SEP 15 2006

PT

JONES, SHEL & FARMER

#5

SCHOEN 'A'

35-3-24W  
SW SW NE

Contr. JONES, SHEL & FARMER

NORTON

County

E 24 1/4 RB Comm. 9-9-54

Comp.

10-8-54

IP

160 BOPD

PERM FMPG

Tops	Depth	Datum
HEEB	3455	-1011
KC	3595	-1151
ARB	3753	-1309
TD	3758	-1314

Casing

8" 275


5" 3754

DST 3754-58/1 HR, 660'

OIL, BHP 660#

CO 3758

NORTON POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS