

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-00669-00-00  
Spot: S2NE Sec/Twnshp/Rge: 35-3S-24W  
1980 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: SCHOEN A Well #: 2  
County: NORTON Total Vertical Depth: 3781 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3773	0	75 SX
SURF	8.625	170	0	125 SX

\$ 122.88

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2006 3:30 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 240 sxs Midcon II cement and 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/08/2006 7:30 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 170' w/125 sxs.  
5 1/2" production casing set at 3773' w/75 sxs.  
Dakota at 1058' - 1358'. Anhy at 2033' - 2053'.  
Casing holes at 1600' - 1800'. Casing fill-up from 3100' - 3781'.  
Ran tubing to 3050' - pumped 75 sxs cement with 300# hulls - no returns.  
Pulled tubing to 1600' - pumped 75 sxs cement with 300# hulls - cement to surface.  
Pulled tubing to surface. Connected to 5 1/2" casing and pumped 20 sxs cement.  
Max. P.S.I. 800#. S.I.P. 0#.  
Connected to 8 5/8" surface casing and pumped 30 sxs cement.  
Max. P.S.I. 75#. S.I. P. 50#.

**Perfs:**

Top	Bot	Thru	Comments
3773	3781		OPEN HOLE

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

RECEIVED (TECHNICIAN)

SEP 25 2006

KCC WICHITA

Form CP-2/3

SEP 15 2006

*PKT*

INVOICED  
DATE 9/26/06  
2007060590

1 WA O I C E P

JONES, SHEL & FARMER #2 SCHOEN 35-3-24W APP C S2 NE  
Contr. \_\_\_\_\_ NORTON \_\_\_\_\_ County


E 2463 RBComm. \_\_\_\_\_ Comp. 12-11-53 IP 258 BOPD  
PERM PMP

Tops	Depth	Datum
HEEB	3473	-1010
TOR	3500	-1037
LANS	3514	-1051
B/KC	3705	-1242
ARB	3771	-1308
TD	3779	-1316

Casing  
5" 3773

20 BOPH, NATL

NORTON POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS