

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24205-00-00
Spot: SENWNENW Sec/Twnshp/Rge: 29-22S-20E
500 feet from N Section Line, 1759 feet from W Section Line
Lease Name: KINCAID Well #: 1-29-22-20
County: ANDERSON Total Vertical Depth: 1160 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1160		235 SX
SURF	8.625	22		4 SX

\$ 37,70

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/09/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Revd. from: LARRY BRYANT Company: CONSOLIDATED OIL WELL SERVI Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SX COTTON SEED HULLS FROM PBSD TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: FRANK GUILFOYLE WitnessType: NONE
Date/Time Plugging Completed: 06/09/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN 2" TUBING TO 1150 FT. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING OUT AND TOP OFF WELL. PUMP TOTAL OF 115 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

RECEIVED
SEP 25 2006
KCC WICHITA

RECEIVED
KCC DISTRICT #3

SEP 21 2006

CHANUTE, KS

FG

INVOICED
DATE 9/27/06
2007060594

Remarks: WELL PLUGGED BY OPERATER

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

PREP