

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24215-00-00  
Spot: S2SWSW Sec/Twnshp/Rge: 26-19S-19E  
330 feet from S Section Line, 500 feet from W Section Line  
Lease Name: GARRISON Well #: 26-14  
County: ANDERSON Total Vertical Depth: 1255 feet

Operator License No.: 33138  
Op Name: MERITAGE KCM EXPLORATION, LLC  
Address: INDEPENDENCE PLAZA 1050 17TH ST  
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1221		165 SX
SURF	8.625	22		4 SX

\$40.79

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/30/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: LARRY BRYANT Company: \_\_\_\_\_ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 700'; CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: NONE  
Date/Time Plugging Completed: 05/30/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN 2" TUBING TO 1200 FT. PUMP 60/40 POZ MIX FROM 1200 FT TO SURFACE. PULL TUBING. TOP OFF WELL. PUMP TOTAL OF 129 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1136	1138		
1118	1120		
1112	1116		
1105	1110		
1073	1075		
1062	1064		
1052	1054		
1033	1035		
1017	1019		
1005	1007		
994	996		
905	909		
890	893		
883	885		
861	864		
846	850		
645	669		

RECEIVED  
SEP 25 2006  
KCC WICHITA

RECEIVED  
KCC DISTRICT #3

SEP 21 2006 FG  
CHANUTE, KS

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

INVOICE  
DATE 9/27/06  
2001060594

District: 03

Signed Frank Guilfoyle  
(TECHNICIAN)

PKT