

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-09304-00-01
Spot: NWNWSW Sec/Twnshp/Rge: 30-9S-18W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SOLENBERGER Well #: 1
County: ROOKS Total Vertical Depth: 3619 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5	3611	0	w/unknown sxs cmt
SURF	8.625	295	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2006 12:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Ran tubing to 1140' - worked thru bridge - hit hard bridge - iron at 1542'.
PTOH. Perforate and run tubing back in to plug.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2006 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated two holes at 1518' and two holes at 1000'.
Ran tubing to 1518'. Allied pumped 175 sxs cement with 500# hulls - circulated cement.
Pulled one joint tubing - got stuck - unable to work free.
Unscrewed tubing at 438'. Pulled out of hole.
Allied pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to backside and pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Note: Left 1104' tubing in the hole.

Perfs:

Remarks: POE TANK SERVICE. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

SEP 21 2006

RECEIVED
Form CP-2/3
SEP 27 2006
KCC WICHITA

HARBAR DRILLING COMPANY

#1

SOLLENBERGER

30-9-18W
NW NW SW

23

Contr. _____ ROOKS _____ Coun

E. 2202 RB Comm. _____ Comp. 2-16-51 IP 360 BOPD

Tops	Depth	Datum
ANH	1570	+632
TOP	3150	-948
HEEB	3319	-1117
DODGE	3338	-1136
LANS	3362	-1160
ARB	3610	-1408
T.D.	3619	-1417

Casing
8" 295 ACID 1500
5" 3610 5 1/2 BOPH

BAUMGARTEN POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

GRANT OIL COMPANY

#1

SELLENBERGER

30-9-18W
NW NW SW

Contr. _____ ROOKS _____ County

E. 2199 Comm. _____ Comp. 8-28-53 IP 199 BOPD

Tops	Depth	Datum
LANS	3362	-1163
ARB	3610	-1411
TD	3619	-1420

Casing
5" 3611 OLD WELL PLUG BACK
OLD TD 3619; PRODUCING FROM ARBUCKLE
PERF 2 1/4/3558-66; BAIL 3/4 BO & 1/3 BWP; ACID 500; SWB 1 BWP; TR OIL; PLUG 3500; PERF 12/3442-46; 12/3470-74; 18/3460-66; SWB 7 BOPH; PERF 27/3401-10; NO INC

+	+	+
---	---	---