

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19161-00-01  
Spot: N2NENWNE Sec/Twnshp/Rge: 21-9S-16W  
5230 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: CASEY Well #: 5W  
County: ROOKS Total Vertical Depth: 3436 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3446	0	w/unknown sxs cmt
SURF	8.625	174	0	w/unknown sxs cmt

Well Type: EOR UIC Docket No: E13728.2 Date/Time to Plug: 09/06/2006 1:00 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-8629

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix and 600# hulls.  
Inj. Zone 3190' - 3358'. DV Tool at 1400' cwc.  
Tubing sticking out of head - amount unknown.  
Backside on vacuum. Tubing ok last MIT. Showed packer set at 3146': (AD-1).

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/06/2006 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

09/01/2006  
Moved in Poe Well Service - worked tubing out of head - pulled 98.5 joints duroline tubing - found parted at 3075' approximate.  
Tubing in good shape, except last 5 scale - parted joint.  
Left 2.5 joints tubing and packer in hole.  
09/06/2006  
Allied pumped 275 sxs 60/40 pozmix with 600# hulls.  
Max. P.S.I. 500#. S.I.P. slight vacuum.  
Hooked up to backside - instant 500#.  
09/07/2006  
Checked cement top 120' down from surface - will cut off and fill with sand and 2 sxs cement on top.

Perfs:

Top	Bot	Thru	Comments
3150	3425		

Remarks: POE TANK SERVICE. \*LEFT 2.5 JOINTS TUBING AND PACKER IN HOLE.

Plugged through: CSG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

SEP 18 2006

RECEIVED  
Form CP-2/3

SEP 27 2006

KCC WICHITA

RECEIVED  
 SEP 27 2006  
 KCC WICHITA

FIELD NO. 11-9415W  
 COUNTY WASH NE BR NE

ENTIRE DRILL LOG  
 FEET 8095  
 COUNTY

LOG NO. 7274/62  
 DATE 8/20/62  
 IP INPUT WELL / LENS-  
 3476/30

DEPTH	DEPTH	Datum	CRISP
ANHY	1330	+ 732	BT 174/100-54 BT 3426
TOP	2927	- 895	OST 2694-2700/1 HR, 215' N, BHP
BASE	3154	-1022	955-7624/30", FP 31-125#.
LOR	3172	-1110	OST 2932-1030/1 HR, 90' N, BHP
LAHS	3192	-1130	1241-074/30", FP 31-62#
			OST 3052-3145/1 HR, NE BR, BHP
			85' NTRY N, SPKS 2, BHP 1014-
			8400/30", FP 39-54#.
			OST 3000-3450/1
LD	3450	-1180	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

T. DANIELSON