

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06596-00-00
Spot: SESENE Sec/Twnshp/Rge: 5-12S-17W
3000 feet from S Section Line, 318 feet from E Section Line
Lease Name: SHUTTS B Well #: 3
County: ELLIS Total Vertical Depth: 3522 feet

Operator License No.: 32754
Op Name: ELYSIUM ENERGY, L.L.C.
Address: 1625 BROADWAY, STE 2000
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3490	0	w/200 sxs cmt
SURF	10.75	1112	0	w/400 sxs cmt

\$ 114.47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2006 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: ELYSIUM ENERGY, LLC Phone: (785) 625-4052

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls - 31 sxs gel (short 3).
Ordered out 200 additional sxs.
Fluid level 1600'. ELI PBD 3470'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2006 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1100'. Ran tubing to 3466'.
Allied pumped 28 sxs gel spacer with 300# hulls, followed with 50 sxs 60/40 pozmix - 10% gel and 200# hulls.
Pulled tubing to 1100'. Allied pumped 180 sxs cement - circulated out 7" - shut in.
Allied pumped 120 sxs - had good circulation out 10 3/4" - ran out of cement.
PTOH while waiting on more cement.
Put 7" swedge on casing and pumped 60 sxs 60/40 pozmix - cement circulated out 10 3/4".

Perfs:

Top	Bot	Thru	Comments
3275	3435		

INVOICED
9/29/06
2007060609

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

SEP 28 2006

KCC WICHITA

Form CP-2/3

SEP 26 2006

ACT