

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20705-00-00
Spot: S2SWNWSW Sec/Twnshp/Rge: 7-35S-33W
1500 feet from S Section Line, 330 feet from W Section Line
Lease Name: HEATHERINGTON Well #: 1
County: SEWARD Total Vertical Depth: 6845 feet

Operator License No.: 102
Op Name: KDOT
Address: _____
_____ KS

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	6409	2422	WITH 215 SX CMT
SURF	8.625	1630		WITH 900 SX CMT

\$ 222.46

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/28/2006 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 6200' WITH 5 SX CMT OR PUMP 400# HULLS & 50 SX CMT & DISPLACE TO 6200'. FREE POINT 5 1/2" CASING AT SHOOT OFF DEPTH PUMP 50 SX CMT. PULL 5 1/2" CASING TO 1660' & PUMP 50 SX CMT. PULL 5 1/2" CASING TO 840' & PUMP 50 SX CMT. PLUG AT 60'-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL
Date/Time Plugging Completed: 08/29/2006 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:


PUMP 400# HULLS & 50 SX CMT. DISPLACE WITH MUD & PRESSURE TO 500#. 1ST PLUG AT 2100' WITH 25 SX CMT. 2ND PLUG AT 1660' WITH 48 SX CMT. 3RD PLUG AT 840' WITH 48 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. GOOD CIRCULATION ON ALL PLUGS.

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

INVOICED
DATE 9/28/06
2007060601
NET. DED. _____

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
SEP 27 2006
KCC WICHITA

Form CP-2/

[Handwritten signature]
[Handwritten initials]