

4-060922

API Number: 15-141-20,320-60-06

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NE NE SE /4 SEC. 11, 10 S, 12 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 6246

Lease: Applegate Well # 1

Operator: Bennett & Schulte Oil Company

County: Osborne

Address: P.O. Box 329  
Russell, Kansas 67665

Well total depth 3310 107.57 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 206 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

9431

Plugging contractor: VonFeldt Drilling Company License#

OK KCC  
apb

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 10 Month: July Year: 1996

Plugging proposal received from: Darrell Krier

Company: VonFeldt Drilling Company Phone:

Were: Order 180 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED  
STATE CORPORATION COMMISSION  
7-15-1996  
JUL 15 1996  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 1:00 P.M. Day: 10 Month: July Year: 1996

Actual plugging report:

- 1st. Plug at 750' w/25 sxs. - Anhydrite 734' - 774'.
- 2nd. Plug at 525' w/80 sxs. - Dakota 268' - 518'.
- 3rd. Plug at 260' w/40 sxs. - Surface pipe to 206'.
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 1718 GL

I did [ ] / did not [ X ] observe the plugging.

*Herb Deines*  
AH (agent)

INVOICED  
DATE 7-22-96  
INV. NO. 46033  
7-10