

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21195-00-00  
Spot: S2S2NW Sec/Twnshp/Rge: 9-23S-17W  
2970 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: STERNE Well #: 1  
County: PAWNEE Total Vertical Depth: 4404 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4398	2215	WITH 150 SX CMT
SURF	8.625	343		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2006 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: RICHARD LACEY Company: KCC Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 4180' & 5 SX CMT. FREEPOINT 5 1/2" PIPE & PULL TO 1100'. SPOT 15 SX GEL & 50 SX CMT. PULL CASING TO 370' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/25/2006 12:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE = 1100'. SANDED TO 4180' & 5 SX CMT WITH DUMP BAILER.  
SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1100' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 370' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.


Perfs:

Top	Bot	Thru	Comments
4342	4350		
4234	4241		

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01



Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED

SEP 29 2006

KCC WICHITA

Form CP-274

*RL*