

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22071-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 12-10S-18W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HARRISON C Well #: 2  
County: ROOKS Total Vertical Depth: 3770 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE ROAD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3450		
DVT		1506		550 SX
PROD	4.5	3768	0	225 SX CMT.
SURF	8.625	288	0	170 SX CMT.

\$122.53

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/18/2006 8:30 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.  
CIBP at 3450'. DV at 1506' w/550 sxs. Sandline Drill CIBP out.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/18/2006 9:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sandline Drill CIBP at 3450'.  
Allied pumped 205 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 800#. S.I.P. 500#.  
Hooked up to backside and pumped 5 sxs - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3598	3602		
3571	3575		
3548	3552		
3529	3533		
3512	3518		
3492	3496		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

VOICE  
DATE 9/28/06  
200.70.60

District: 04

Signed Richard Williams  
(TECHNICIAN)

SEP 21 2006

RECEIVED  
Form CP-2/3  
SEP 27 2006  
KCC WICHITA

FRONTIER OIL COMPANY  
1720 KSB&T BUILDING

#2 "C" HARRISON

12-10-18W  
NW SW NE

WICHITA, KS 67202

CONTR RED TIGER DRILLING CO.

CTY ROOKS

GEOLOGICAL STEVE PARKER


FIELD PLAINVILLE

ELV 2131 KB SPD 7/22/83

CARD ISSUED 10/13/83

IP OIL WELL

LKC 3492-3602 OA



API 15-163-22,071

SMP	Tops	Depth/Datum	
ANH	1468+	663	8 5/8 " 288/170SX; 4 1/2 " 3768/225SX; DV TOOL SET
BRNVLE	2788-	657	DST (1) 3343-3438 (TOR, LKC) / 30-30-30-30, REC 5' M, SIP 215-158#, FP 79-79 / 79-79#
TARK	2888-	757	DST (2) 3463-3522 (LKC) / 60-30-60-30, REC 10' M, W/OIL SPKS, SIP 80-68#, FP 57-57 / 57-57#
HOW	3063-	932	DST (3) 3520-3615 (LKC) / 60-30-60-30, REC 256' WM, SIP 1164-1040#, FP 170-182 / 182-182#
TOP	3093-	962	MICT - CO, DRLD DV TOOL, PF (LKC) 1/ 3600, 1/ 3573, 1/ 3549, AC 1500G (15% REG), SWB DWN & REC 2.32 BF (30% OIL), RE-PF (LKC) 4/ 3598-3602, 3571-75, 3548-52 W/4 SPF, & 1/ 3531, 1/ 3494, SET PLUG AT 3542, AC 1500G (15% REG DEMUL), SWB DWN & REC 2 BF (30% OIL), RE-PF (LKC) 3529-33, 3512-18, 3492-96 W/4 SPF, ONFU 400' FL, SWB DWN & REC 6.96 BF (40% OIL), DRLD PLUG TO BTM, POP, 9/9/83
HEEB	3311-	1180	
TOR	3331-	1200	
LANS	3354-	1223	
BKC	3605-	1474	
CHT CONG	3607-	1476	
SIMP DOL	3667-	1536	
ARB DOL	3709-	1578	
RTD	3770-	1639	

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS