

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20029-00-00
Spot: SENENW Sec/Twnshp/Rge: 6-2S-18W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FAUBION Well #: 1
County: PHILLIPS Total Vertical Depth: 3668 feet

Operator License No.: 3077
Op Name: JOHNSON OIL, A GENERAL PARTNERS
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	2.375	3437	0	425 SX
PROD	4.5	3662	0	425 SX
SURF	8.625	216	0	155 SX

\$119.21

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2006 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Ordered out 105 sxs common cement.
Plugging Squeeze job: 1987 casing leak at 1493' squeezed with 50 sxs.
Method: 07/14/2006 - cemented tubing in the hole. Swift Services pumped 425 sxs 60/40 pozmix - 6% gel cwc. CIBP at 3438'. Tubing at 3437'. Lost bottom of the hole - decided to P/A.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2006 12:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 1" PVC down backside - tagged cement 50' down.
Pumped 12 sxs common cement.
Pumped 54 sxs common cement down tubing.
Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3526	3569		
3516	3520		
3474	3478		

Remarks:

Plugged through: TBG

INVOICED
DATE 9/28/06
2007060606

District: 04

Signed Richard Williams
(TECHNICIAN)

SEP 21 2006

RECEIVED Form CP-2/3
SEP 27 2006
KCC WICHITA *RET*

032010

M & B ENTERPRISES #1 FAUBION 6-2-18W
 SE NE NW
 Contr. RED TIGER DRLG Cty. PHILLIPS
 Geol. R. P. NIXON Pool HUFFSTUTTER
 E. 2269 KB Cm. 1/22/68 Cp. 4/11/68 IP P 10 BOPD, NW
 LANS 3476-3568
 API 15-147-20,029

LOG Tops	Depth	Datum	Csg.
			8" 4" 3652
HEEB	3389	-1120	DST 3473-3535/1', 30' M/SP OIL BHP 151-127#/30", FP 0-0#
TOR	3423	-1154	
LANS	3438	-1169	DST 3562-3600/30", 4' MO, 1' FREE OIL, FBHP 170#/30", FP 0-0#
BKC	3659	-1390	
RED	3668	-1399	CO & PF 4/3566-68, 2000 REG 1000 RETARDED A, PF 4/3528-30, A 2000 + 1000, 4/3517-19, ACID 2000, 4/3476-78, ACID 2000 + 1000, SWB LD, SWB 1/2 BF, PMP 38 BFPD 85% OIL, POP.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS