

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20061-00-01  
Spot: SWNE Sec/Twnshp/Rge: 20-4S-19W  
3300 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: KINTER Well #: 3  
County: PHILLIPS Total Vertical Depth: 1318 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: P.O. BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1318	0	350 SX
SURF	8.625	170	0	150 SX

\$42.84

Well Type: SWD UIC Docket No: D14924.0 Date/Time to Plug: 09/19/2006 10:00 AM  
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION  
Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 476-5254

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Fluid 300' down. 5 1/2" casing cemented from 1318' to surface with 350 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/19/2006 11:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 150 sxs 60/40 pozmix - 10% gel with 600# hulls.  
Max. P.S.I. 100#. S.I.P. 0#. Slight vacuum. Shut in 30 minutes.  
Allied pumped 50 sxs cement.  
Max. P.S.I. 100#. S.I.P. 50#. Hole full.  
Backside full of cement.  
09/20/2006 - Cement 10' from surface.

Perfs:

Top	Bot	Thru	Comments
1032	1196		

INVOICED

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

DATE: 9/28/06  
WT. NO. 200706060.3

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

*td*

RECEIVED

SEP 27 2006

KCC WICHITA

Form CP-2/3

SEP 21 2006

*PKT*

THE R. W. RINE DRILLING CO. #3 KINTER 20-4-19W  
 WICHITA, KS. C SW NE  
 Contr. MURFIN DRLG. CO. Cty. PHILLIPS  
 Geol. PAUL HARPER Pool KINTER

E. 1943 KB Cm. 1/21/69 Cp. 5/22/69 IP WTR. INJECT/CHEY.  
 SD 1032-1200  
 (OVER-ALL)

SMP Tops	Depth	Datum	Csg. 8-5/8" 170/150 SX 5 1/2" 1318/350 SX
CHEY SD	1030	+ 913	
ANH	1480	+ 463	DST 3106-40/1', 85' WM, BHP
HEEB	3100	-1157	930-796#/30", FP 36-63#
TOR	3125	-1182	DST 3173-82/1', 65' SOCM, BHP
LKC	3142	-1199	984-662#/30", FP 45-63#
BKC	3362	-1419	DST 3186-3225/45", 5' DRLG M,
MARM LM	3412	-1469	BHP 1190-1118#/30", FP
RTD	3529	-1586	29-45#
			DST 3302-26/45", 15' M (NS)
			BHP 215-63#/30", FP 32-32#
			CO PF (CHEY SD) 1200, 1196, 1192,
			1180, 1162, 1158, 1144, 1142,
			1138, 1130, 1120, 1118, 1116, 1108
			1090, 1033, 1076, 1066, 1052, 1050
			1032, A 1000, INJ RATE 11 BPM
			MP 500#, IR 1/2 BPM (APPX 720 BWPD)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS