

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21789-00-00
Spot: SESW Sec/Twnshp/Rge: 24-32S-43W
660 feet from S Section Line, 2100 feet from W Section Line
Lease Name: SMITH TRUST Well #: 1-24
County: MORTON Total Vertical Depth: 5160 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 15 E. 5TH, SUITE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1470		

\$ 167.70

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/21/2006 7:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY WILSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 3350' WITH 100 SX CMT. 2ND PLUG AT 1470' WITH 50 SX CMT. 3RD PLUG AT 480' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 09/21/2006 9:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:


1ST PLUG AT 3350' WITH 100 SX CMT. 2ND PLUG AT 1470' WITH 50 SX CMT. 3RD PLUG AT 480' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed

Steve Durrant

(TECHNICIAN)

[Handwritten signature]