

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 113-20,665 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 11/24/79.

Well Operator: K & S Oil (Owner / Company Name) KCC License #: 32381 (Operator's)
Address: 1520 N Grimes City: McPherson
State: Kansas Zip Code: 67460 Contact Phone: (620) 241 - 4901
Lease: Decker Well #: 1 Sec. 2 Twp. 19 S. R. 1 East West
NE - SE - NW - Spot Location / QQQQ County: MP

1850 3679 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2310 3041 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)
GPS-KCC-DIG

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 168' Cemented with: 125 Sacks
Production Casing Size: 5 1/2 Set at: 2900' Cemented with: 50 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforated in Mississippi at 2847-55'

Elevation: 1518 (G.L. / K.B.) T.D.: 2901 P.B.T.D.: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand off perms to 2775' and bail in 5 sacks cement on top of sand bridge. Rip Casing at 2350' and pull out. Build bridge at 250' and fill with cement.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jay Krehbiel

Phone: (620) 241 - 4901

Address: 1520 N Grimes City / State: McPherson, KS 67460

Plugging Contractor: Mike Kelso KCC License #: 315289
(Company Name) (Contractor's)

Address: P. O. Box 467 Chase, KS 67524-0467 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): 8/28/06 1:00pm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-13-06 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* well already plugged - kcc-dig

RECEIVED
AUG 17 2006
KCC WICHITA


BRUCE OIL CO.
 BOX 1, ROUTE #4 #1 DECKER 2-19-1W
 MCPHERSON, KS NE SE NE W/W?

CONTR TRIANGLE DRLG CTY MCPHERSON

GEOL H. C. HOPKINS FIELD KOEHN

E 1518 KB CM 11/24/79 CARD ISSUED 2/7/80 IP P 64 BO & 95 BWP
 & EST 20 MCFGPD
 MISS 2847-55

API 15-113-20,665



LOG	TOPS	DEPTH	DATUM
LANS		2254	- 736
KC		2425	- 907
BKC		2608	-1090
CHER		2798	-1280
BURG SD		2823	-1305
CONG		2834	-1316
MISS		2838	-1320
RTD		2901	-1383

8-5/8" 168/125sx, 5 1/2" 2900/50sx

NO DST'S
 MICT - CO, PF (MISS) 2847-55, AC 750
 (7 1/2%), SWB DWN W/SO & G, EST 200
 MCFGPD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 AUG 17 2008
 KCC WICHITA