

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING REPORT  
 K.A.R.-82-3-117

API NUMBER 15-141-203200000

LEASE NAME Applegate

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 10S RGE. 12W (E) or (W)

COUNTY Osborne

Date Well Completed 7-10-96

Plugging Commenced 7-10-96

Plugging Completed 7-10-96

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bennett & Schulte Oil Company

ADDRESS P.O. Box 329, Russell, Kasnas 67665

PHONE# (913) 483-2721 OPERATORS LICENSE NO. 6246

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-10-96 (date)  
 by Hays (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from    feet to    feet each s  
Plugged with 180 sacks 60/40 Poz., 6% Gel., and 1/4# floseal per sack - 1st. plug @ 750' with  
25 sacks - 2nd. plug @ 525' with 80 sacks - 3rd. plug @ 260' with 40 sacks - wiper plugged  
@ 40' with 10 sacks to surface - mouse hole with 10 sacks - rat hole with 15 sacks.

Name of Plugging Contractor Vonfeldt Drilling Co. Kd. of B. Bennett & Schulte Oil Co. License No. 9431 325

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bennett & Schulte Oil

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.


Bennett & Schulte Oil Co. (Frank Schulte) (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fac  
 statements, and matters herein contained and the log of the above-described well as filed i  
 the same are true and correct, so he certifies under penalty of perjury.

RECEIVED  
 KANSAS CORPORATION COMMISSION

8-28-1996 (Signature) Frank Schulte

AUG 28 1996 (Address)

SUBSCRIBED AND SWORN TO before me this 27 day of August, 19 96



Pamela K. Smith  
 Notary Public

USE ONLY ONE SIDE OF EACH FORM

COPY

ORIGINAL

DRILLERS WELL LOG

Date Commenced: July 5, 1996  
Date Completed: July 10, 1996

Bennett & Schulte Oil Company  
Applegate #1  
NE NE SE Sec. 11-10S-12W  
Osborne County, Kansas

Elevation: 1718' G.L.  
1723' K.B.

15-141-20320-00-00

0 - 330' Sand & Clay  
330 - 743' Sand, Shale & Redbed  
743 - 774' Anhydrite  
774 - 1100' Shale  
1100 - 2770' Shale & Lime  
2770 - 2970' Kansas City  
2970 - 3000' Lime & Shale  
3000 - 3260' Kansas City  
3260 - 3310' Kansas City & Lansing  
3310' R.T.D.

FORMATION DATA

Anhydrite	743'
Base Anhydrite	774'
Topeka	2659'
Heebner	2899'
Toronto	2923'
Lansing	2955'
Base Kansas City	3284'
T.D.	3310'

Surface Pipe: Set 20#, used, 8 5/8" tally  
@ 206' with 140 sacks 60/40 Poz., 2%  
Gel., 3% CC.

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 28 1996

**AFFIDAVIT**

CONSERVATION DIVISION  
WICHITA, KS

STATE OF KANSAS  
COUNTY OF RUSSELL) ss

Alan Vonfeldt of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

Alan Vonfeldt  
Alan Vonfeldt

Subscribed and sworn to before me this 12<sup>th</sup> day of July, 1996.

My Commission Expires:

August 30, 1999  
Cheryl M. Payne  
Cheryl M. Payne, Notary Public

