

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Range Oil Company, Inc.  
Address: 125 N Market, Suite 1120, Wichita, KS 67202  
Phone: (316) 265-6231 Operator License #: 5120  
Type of Well: EOR Per RBDms PFT KCC 10/2/06 Docket #: E-20, 670  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Doug Louis (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 035-21, 212 -00 -01  
Lease Name: Hammer  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - W/2 - NW - SE  
1980 Feet from  North /  South Section Line  
2310 2424 Feet from  East /  West Section Line  
Sec. 6 Twp. 33 S. R. 6  East  West  
County: Cowley  
Date Well Completed: 8-4-77 original  
Plugging Commenced: 9-19-06  
Plugging Completed: 9-20-06

KCC  
PFT  
10/2/06  
Per  
PFGS  
Copsid

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	157	
				4 1/2	3105	1010


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3000', baled 4 sacks cement with baler, dug cellar, unpacked casing head, set floor, pulled slips, had 8" stretch,  
ripped casing at 1230', worked pipe, ripped casing at 1010', pipe came free, pulled casing up to 350', circulated cement with 151 sacks,  
pulled rest of casing, hole stayed full

Name of Plugging Contractor: Quality Well Service License #: 31925  
Address: 401 W Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Range Oil Company, Inc.  
State of Kansas County, Sedgwick, ss.  
John M. Washburn (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John M. Washburn  
(Address) 125 N. Market, Suite 1120 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 28th day of September, 2006  
Peggy L. Sailor My Commission Expires: 12-8-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
SEP 29 2006  
KCC WICHITA

# Quality Well Service, Inc.

401 West Main  
Lyons, KS 67554

# Invoice

Date	Invoice #
9/26/2006	805

Bill To
Range Oil Co., Inc. 125 N. Market, Suite 1120 Wichita, KS 67202

P.O. No.	Terms	Lease Name
	net	Hammer 1

Description	Qty	Rate	Amount
Rig Time	13.5	155.00	2,092.50T
Trucking Floor		100.00	100.00T
Sand		35.00	35.00T
Cement	4	9.00	36.00T
Shots	2	150.00	300.00T
Water Truck	4.5	70.00	315.00T
Out of Town		120.00	120.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
9-19-06 Drove to location, raised pole, checked hole, sanded off bottom, loaded hole with water, drove to motel.			
9-20-06 Drove to location, checked hole, sand was at 3000', baled 4 sacks cement with baler, had backhoe dig cellar, unpacked casing head, set floor, pulled slips, had 8" stretch, ripped casing at 1230', worked pipe, ripped casing at 1010', pipe came free, pulled casing up to 350', circulated cement with 151 sacks, pulled rest of casing, hole stayed full, tore down floor and rig.			
<b>Subtotal</b>			\$3,053.50
<b>Sales Tax (5.8%)</b>			\$177.10
<b>Total</b>			\$3,230.60

RECEIVED  
SEP 26  
KCC WICHITA

# United Cementing & Acid Company, Inc.

2510 W. 6th St.  
 El Dorado, Kansas 67042  
 316-321-4680 800-794-0187 (Fax) 316-321-4720

**INVOICE**

Customer:

**Range Oil Company, Inc.**  
 125 N. Market St., Ste. 1120  
 Wichita, KS 67202

Invoice No. **7793**  
 Field Ticket **7246**  
 Date **9/26/2006**  
 PO#

Date of Job	County	State	Lease	Well No.
09/20/06	Cowley	KS	Hammer	#1
Size of Casing	Depth Of Well	Depth Of Job	Plug Depth	Pressure
4-1/2"	3141'			
Quantity	Description	UOM	Unit Price	Total
	<b>OLD HOLE PLUG</b>			
151	60/40 Pozmix	sax	6.25	943.75
6	Gel	sax	11.00	66.00
157	Bulk charge	sax	1.05	164.85
	Drayage - 7.85 tons			320.28
48	Mileage charge	mi	2.25	108.00
	Service Charge			550.00
			<b>Sub-Total</b>	<b>2,152.88</b>
	<i>Thank you for your continued business</i>			
Taxable	*Non-Taxable	Tax Rate	Sales Tax	TOTAL DUE
2152.88	0.00	0.058	124.87	<b>\$2,277.75</b>

TERMS: Net 30 days from invoice date. Please pay from this invoice.

**RECEIVED**

SEP 29 2006

**KCC WICHITA**

ORIGINAL INVOICE