

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21371-00-00

Spot: NWNWSE Sec/Twnshp/Rge: 22-31S-1E
2188 feet from S Section Line, 2518 feet from E Section Line

Lease Name: STEWART Well #: 1-22

County: SUMNER Total Vertical Depth: 3990 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3988		
SURF	8.625	250		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2006 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand off both sets of perfs and circ cmt inside and outside of 4-1/2".

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/26/2006 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Sanded back bottom perforations to 3850' and capped with 4 sacks of cement. Pushed wooden plug below top perforations and sanded back to 3440'. Capped with 4 sacks of cement. Ran 1" tubing down backside of 4-1/2" casing to 300'. Pumped 175 sacks of cement. Ran 1" inside of 4-1/2" casing to 300' and pumped 25 sacks of cement.

United Cement #7248
60/40 posmix with 4% gel

Perfs:

RECEIVED
KCC DISTRICT #2
SEP 27 2006
WICHITA, KS

Remarks: CONTROL # 2006-0067-001

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

PKT