

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-25151-00-00
Spot: NWNENW Sec/Twnshp/Rge: 30-29S-15E
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: CREAGER Well #: 1
County: WILSON Total Vertical Depth: 1265 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1250	0	130 sx
SURF	8.625	20	0	5 sx

\$ 411.11

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2004 8:00 AM
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.
Proposal Revd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed Plugging Method: Run a cement string to TD and fill well from bottom to top with portland cement.

Plugging Proposal Received By: ALAN DUNNING Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2004 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered to 1250 ft. The well was filled from bottom to top thru this one inch cement string. The cement string was removed and the well topped off with cement. Altogether, 125 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
997	1003		

RECEIVED
KCC DISTRICT #3
SEP 26 2006
CHANUTE, KS

INVOICED
10/4/06
DATE 2007060628

RECEIVED
OCT - 2 2006

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)

AS