

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-01267-00-00  
Spot: SENWSWSE Sec/Twnshp/Rge: 34-31S-15E  
710 feet from S Section Line, 2306 feet from E Section Line  
Lease Name: TALLMAN Well #: OW 1-34  
County: MONTGOMERY Total Vertical Depth: 575 feet

Operator License No.: 33074  
Op Name: DART CHEROKEE BASIN OPERATING  
Address: 600 DART RD PO BOX 177  
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	575	0	
SURF	10	20		20 ft is an estimate

\$35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2006 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed Plugging Method: Run 1 inch cement strings inside and outside of production pipe to TD and then fill from bottom to top with portland cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 05/15/2006 12:00 PM KCC Agent: ALAN DUNNING

**Actual Plugging Report:**

A one inch cement string was lowered down the inside of the 2 inch pipe to 575 ft. A one inch cement string was lowered down the outside of the 2 inch pipe to 300 ft. The well was filled from bottom to top thru these cement strings. The cement strings were removed and the well topped off with cement. Altogether, 245 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

**Perfs:**

RECEIVED  
KCC DISTRICT #3  
SEP 27 2006  
CHANUTE, KS

INVOICED  
DATE 10/4/06  
2007060628

RECEIVED  
OCT - 2 2006  
KCC WICHITA

Remarks:  
Plugged through: TBG

District: 03

Signed Alan Dunning  
(TECHNICIAN)

PKT