

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01713-00-01
Spot: SWNENW Sec/Twnshp/Rge: 23-12S-16W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: DREILING Q OWWO Well #: 5
County: ELLIS Total Vertical Depth: 3365 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVENUE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3355	0	w/175 sxs cmt
SURF	8.625	200	0	w/130 sxs cmt

\$ 109.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2006 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: IVAN EDSEL Company: DREILING OIL, INC. Phone: (785) 735-2289

Proposed Plugging Method: Ordered 305 sxs 60/40 pozmix - 10% gel and 800# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2006 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Pressured up backside.
P.S.I. 100# - no cement.
Pumped 280 sxs 60/40 pozmix - 10% gel with 800# hulls.
Max. P.S.I. 700#. S.I.P. 350#.

Perfs:

INVOICED
DATE 10/4/06
INV. NO. 2007060629

Remarks: ALLIED CEMENTING COMPANY-TICKET #21368.

Plugged through: CSG

District: 04

HD

Signed _____

Marvin Mills
(TECHNICIAN)

RECEIVED

Form CP-2/3

OCT - 2 2006

KCC WICHITA

SEP 28 2006

PFT

replacement card

DREILING OIL
VICTORIA KS

23-12S-16W
SW NE NW

5 DREILING Q OWWO

site: 2-1/2 N & 3-1/4 E OF EMMERAM KS ay: ELLIS API 15-051-01713

contr: DREILING OIL field: BLUE HILL

geol:

fr spd drig card last
date 06/10/80 date 06/21/80 comp 06/21/80 issued 10/23/80 revised 02/16/98

ELV: 1865 KB, 1862 DF SMP
 tops.....depth/datum
 * ANH.....1010 + 855
 * B/ANH.....1047 + 818
 * FT RILEY.....1615 + 250
 HEEB.....3025 -1160
 TOR.....3044 -1179
 LANS.....3073 -1208
 PBSD.....3120 -1255
 PENN BASAL SD.....3325 -1460
 ARB.....3352 -1487
 RTD OLD.....3446 -1581
 * DRILLER TOP

IP status:
 OIL, FORM , INTV NA , 10/15/80
 INFO RELEASED: 2/16/98 - WAS TIGHT HOLE
 OLD INFO: OPERATOR WAS R P NIXON OPERATIONS,
 2 SMITH, SPD 09/25/59 , 10/02/59 8-5/8" 200, 5-1/2" 3355,
 OIL, P 25 BOPD, SHAW 2807-2813 , LKC 3075-3108 OA ,
 09/25/59 (CARD ISSUED 10/02/59)
 CONTR. A L JACKSON DRLG
 COMMENT. WAS API IOG-2465
 DRLR SD ZNS. 380-470, 470-490 (W/IRON), 490-525,
 525-800 (M-STLY SH, W/SD)

NO CORES OR DSTS

MICT - CO, (ARB OH), AC 1000 GAL, SWB 1.75 BOPH/4 HRS, SET PLUG AT 3340, PF (PENN BASAL SD) 16/3325-3329, AC 1000 GAL, SWB 5 BFPH (15% OIL)/8 HRS, SET PLUG AT 3300, PF (LKC) 20/3103-3108, AC 500 GAL, SWB 9 BFPH (18% OIL), SET PLUG AT 3100, PF (LKC) 3075-3082, AC 500GAL, SWB 0.5 BFPH (5% OIL)/3 HRS, SET PLUG AT 2900, PF (TOP) 24/2807-2813, AC 1000 GAL, SWB 1 BFPH (50% OIL)/5 HRS, CO 3120 PBSD, POP, IPP 25 BOPD, 9/25/59, COMMINGLED

NEW INFO: FR 06/10/80 , RE-ENTERED 06/21/80 WSH DWN DC 06/21/80 CSG: PROD CSG ALREADY IN HOLE MICT - CO, PF (FORM & INTV NA), SO, POP, OIL WELL (POTENTIAL NOT RPTD), 10/15/80 - NO OTHER INFO RELEASED BY OPERATOR OR ON KCC RECORDS (NO ACO, NO PLUG RPT); ALL REQUESTS FOR INFO DENIED