

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21765-00-00

Spot: E2E2SE

Sec/Twnshp/Rge: 23-12S-16W

1320 feet from S Section Line,

330 feet from E Section Line

Lease Name: DREILING Q

Well #: 2

County: ELLIS

Total Vertical Depth: 3415 feet

Operator License No.: 5145

Op Name: DREILING OIL INC

Address: 1008 CODY AVENUE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

CIBP		3350		
------	--	------	--	--

PROD	4.5	3413	0	175 SX
------	-----	------	---	--------

SURF	8.625	167	0	100 SX
------	-------	-----	---	--------

\$110.99

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/27/2006 9:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: IVAN EDSEL

Company: DREILING OIL, INC.

Phone: (785) 735-2289

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 10% gel and 800# hulls.
Pump down backside.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/27/2006 10:30 AM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto backside - pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 100#.
Tied on top casing - pumped 230 sxs cement with 800# hulls.
Max. P.S.I. 700#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3369	3372		
3356	3360		
3340	3344		
3114	3118		
3088	3092		

Remarks: ALLIED CEMENTING COMPANY-TICKET #21367.

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

SEP 28 2006

RECEIVED

OCT - 2 2006

KCC WICHITA

Form CP-2/3

PKT

DREILING OIL, INC.

RT. #1

VICTORIA, KS 67671

CONTR DREILING OIL, INC.

CTY ELLIS

#Q-2 DREILING

23-12-16W

C E/2 E/2 SE

GEOL

FIELD BLUE HILL SE

E 1873 KB CM 8/22/79 CARD ISSUED 11/3/79 IP P 5 BO & 25 BWPD
ARB 3356-60

API 15-051-21,765

LOG	TOPS	DEPTH	DATUM
ANH		1007	+ 866
TOP		2764	- 891
HEEB		3034	-1161
TOR		3057	-1184
LANS		3086	-1213
B KC		3326	-1453
ARB		3348	-1475
RTD		3415	-1542

8-5/8" 167/110sx, 4 1/2" 3413/175sx

NO DST'S
MICT - CO, PF (ARB) 3356-60, AC 500,
SWB 2.09 BO/60", ONFU 800' FL (500' O
& 300' W), POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS