

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22978-00-00
Spot: NWNWNENW Sec/Twnshp/Rge: 23-12S-16W
300 feet from N Section Line, 1475 feet from W Section Line
Lease Name: DREILING Q Well #: 6
County: ELLIS Total Vertical Depth: 3475 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVENUE PO BOX 550
HAYS, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3472	0	175 SX
SURF	8.625	166	0	130 SX

\$ 112.94

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2006 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: IVAN EDSEL Company: DREILING OIL, INC. Phone: (785) 735-2289

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel and 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2006 12:50 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Hooked on backside - pressured up to 200# P.S.I. - no cement.
Pumped 280 sxs 60/40 pozmix with 800# hulls.
Max. P.S.I. 900#. S.I.P. 550#.

Perfs:

INVOICED
DATE 10/4/06
REF. NO. 2007060629

Remarks: ALLIED CEMENTING COMPANY-TICKET #21369.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

RECEIVED

Form CP-2/3

OCT - 2 2006

KCC WICHITA

SEP 28 2006

DREILING OIL, INC.

REPLACEMENT CARD

23-12-16W

RT. #1

#6 "Q" DREILING

300'FNL&

VICTORIA, KS 67671
CONTR COMPANY TOOLS

CTY ELLIS

1475'FWL, NW/4

GEOL

FIELD BLUE HILL

+	+
+	+
+	+

ELV 1979 KB SPD 4/20/83 CARD ISSUED 8/19/82 IP P 10 BO & 20 BWPD
1974 GL ARB 3384-3388
API 15-051-22,978

DRLRS	Tops	Depth/Datum
ANH		1018 + 961
B/ ANH		1062 + 917
NO OTHER TOPS AVAILABLE		
RTD		3475-1496

8 5/8 " 166/130SX; 5 1/2 " 3472/175SX
NO DST'S
NS IN SD FROM 405-520
MICT - CO, PF (ARB) 4/ 3384-88, AC 250G (15% MA), SWB LD,
GSO, PF (DAK) INTV NA, SQZ'D W/400SX, SET 2 1/2 " TBG AT
3445, POP, P 10 BO & 20 BWPD (GR 28.5°), 5/18/82 - NO OTHER
INFO TO BE RELEASED BY OPERATOR

CORRECTION & INFO RELEASED: 7/7/83 - ORIGINALLY FIRST RE-
PORTED 175'W, C NW NE NW; WAS LKC OIL WELL - TIGHT HOLE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS