

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-005-20106-00-00  
Spot: SENESWSE Sec/Twnshp/Rge: 32-6S-21E  
785 feet from S Section Line, 1395 feet from E Section Line  
Lease Name: WALNUT Well #: 32-2  
County: ATCHISON Total Vertical Depth: 1518 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1503	0	180 SX CMT
SURF	8.625	188	0	105 SX CMT

\$49.34

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1484' TO 1370', CEMENT FROM 1370' TO 1125', FEL FROM 1125' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 03/09/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1470' then pumped 11.25 barrels of gel. Had gel from 1470' to 1360'. Pulled the tubing up to 1360' and pumped 13.5 barrels of gel and 30 sacks of cement with 1 sack of cottonseed hulls. Had cement from 1360' to 1098' and gel from 1098' to 275'. Pulled the tubing to 274' and circulated 30 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1319	1320		
1304	1306		
1250	1255		
1204	1205		
1185	1186		
1175	1176		

RECEIVED  
KCC DISTRICT #3

SEP 27 2006 TCH

CHANUTE, KS

INVOICE  
DATE 10/4/06  
NO. 2007060630

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED  
OCT - 2 2006  
KCC WICHITA

Form CP-2/3

PKT