

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20107-00-00
Spot: S2NE Sec/Twnshp/Rge: 33-6S-21E
1882 feet from N Section Line, 1373 feet from E Section Line
Lease Name: WALNUT Well #: 33-1
County: ATCHISON Total Vertical Depth: 1582 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1576	0	160 SX CMT
SURF	8.625	201	0	98 SX CMT

\$ 51.42

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/01/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1490' TO 1454', CEMENT FROM 1454' TO 1194', GEL FROM 1194' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 03/01/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1490' then pumped 10 barrels of gel. Had gel from 1490' to 1458'. Pulled the tubing up to 1459' and pumped 10 barrels of gel and 30 sacks of cement with 1 sack of cottonseed hulls. Had cement from 1459' to 1117' and gel from 1117' to 275'. Pulled the tubing to 274' and circulated 30 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1402	1404		
1388	1390		
1330	1334		
1257	1258		
1254	1255		
1244	1246		

RECEIVED
KCC DISTRICT #3

SEP 27 2006 TCH

CHANUTE, KS

10/4/06
2007060630

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

RECEIVED
OCT - 2 2006
KCC WICHITA

Form CP-2/3

PCP