

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-005-20105-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 32-6S-21E  
1995 feet from N Section Line, 1657 feet from E Section Line  
Lease Name: WALNUT Well #: 32-1  
County: ATCHISON Total Vertical Depth: 1575 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1570	0	153 SX CMT
SURF	8.625	136	0	82 SX CMT

*\$51.19*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/06/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Revd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1541' TO 1497', CEMENT FROM 1497' TO 1212', GEL FROM 1212' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 03/06/2006 12:00 AM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

Ran tubing and tagged bottom at 1541' and pumped 15 barrels of gel. Gel was placed from 1541' to 1492'. Pulled the tubing to 1492' and pumped 22 barrels of gel and 35 sacks of cement with 1 sack of cottonseed hulls. Had cement from 1492' to 1204' and gel from 1204' to 275'. Pulled the tubing to 286' and circulated 30 sacks of cement to surface.

**Perfs:**

Top	Bot	Thru	Comments
1446	1447		
1385	1387		
1369	1371		
1311	1315		
1262	1264		

RECEIVED  
KCC DISTRICT #3

SEP 27 2006 TCH

CHANUTE, KS

INVOICE  
DATE 10/4/06  
WT. NO. 2007060630

Remarks:

Plugged through: TBG

District: 03

Signed

*Taylor C. Herman*

(TECHNICIAN)

RECEIVED  
OCT - 2 2006  
KCC WICHITA

Form CP-2/3

*PBT*