

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-005-20108-00-00  
Spot: E2SWNW Sec/Twnshp/Rge: 33-6S-21E  
2063 feet from N Section Line, 1060 feet from W Section Line  
Lease Name: WALNUT Well #: 33-2  
County: ATCHISON Total Vertical Depth: 1580 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1577	0	143 SX CMT
SURF	8.625	197	0	230 SX CMT

\$51.35

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1549' TO 1452', CEMENT FROM 1452' TO 1276', GEL FROM 1276' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 03/02/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1543' then pumped 11 barrels of gel. Had gel from 1543' to 1448'. Pulled the tubing up to 1448' and pumped 14 barrels of gel and 20 sacks of cement with 1 sack of cottonseed hulls. Had cement from 1488' to 1273' and gel from 1273' to 274'. Pulled the tubing to 284' and circulated 30 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1400	1402		
1384	1386		
1326	1330		

RECEIVED  
KCC DISTRICT #3

SEP 27 2006

CHANUTE, KS

TCM

INVOICED  
DATE 10/4/06  
INV. NO. 20070606 30

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED  
OCT - 2 2006  
KCC WICHITA

*PH*