

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

00-02 KCC WICHITA 10-06-06

API # 15 - 151-21,604-~~0004~~ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 06/22/1985

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056

Address: 9431 E. Central, St. 100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481

Lease: HISKETT Well #: 1-14 Sec. 14 Twp. 29 S. R. 11 East West

C - SW - SE - SW Spot Location / QQQQ County: Pratt

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 266' Cemented with: 210 Sacks

Production Casing Size: 4-1/2" Set at: 4745' Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2664'-2671', 4642'-43,

Elevation: 1779 (G.L. / K.B.) T.D.: 4760' PBTD: 4715' Anhydrite Depth: 605'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy Mud, hulls, cement and plug according to KCC regulations.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rob Long

Phone: (620) 793 - 0915/786-5783

Address: P.O. Box 158 City / State: Belpre, KS. 67519

Plugging Contractor: Quality Well Service KCC License #: 31925

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 11/03/2005 Authorized Operator / Agent: Loveness Mpanje
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

6/06

8/06

RECEIVED
NOV 07 2005
KCC WICHITA

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HISKETT #1-14

Located: SW SE SW, Section 14-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 17, 1985

COMPLETED: May 26, 1985

TOTAL DEPTH: 4760'

LOG

0 - 41 Surface Soil and Sand
41 - 130 Sand, Clay
130 - 269 Shale
269 - 900 Shale, Sand, Red Beds
900 - 1775 Shale and Lime Str.
1775 - 4760 Lime and Shale

CASING RECORD

Ran 6 joints new 8 5/8", 23# casing.
253.27' pipe set at 266' K. B. Cemented
with 210 sacks 60/40 Pozmix with 3% cc.
Plug down at 7:30 PM, 5-17-85, by Howco.

Ran 119 joints 4 1/2", 10.5# OD casing.
14 joints were used. 4745.39; pipe
set at 4745' K.B. Cemented with 100
sacks Lite and 125 sacks 50/50 Pozmix,
plus our regular additives and flush
ahead at T.D. 125 sacks 50/50 Pozmix
plus our regular additives and 10 bbls.
salt water flush at 2800'. First plug
down at 3:45 PM, 5-26-85, by Howco.
Second plug down at 4:45 PM, 5-26-85,
by Howco. First plug is at 4731' K.B.
Second plug is at 2804' K.B.
Plugged rathole. Water well assigned
to farmer.

RECEIVED

MAY 07 1985

KCC WICHITA

Deviation Surveys: 3/4° at 1932'
3/4° at 2685'
3/4° at 4130'
1 1/2° at 4560'

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
9431 E Central, Suite 100
Wichita, KS 67206

November 08, 2005

Re: HISKETT #1-14
API 15-151-21604-00-~~02~~02
SWSESW 14-29S-11W, 330 FSL 3630 FEL
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor