

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

RECEIVED

APR 03 2006

KCC WICHITA

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 041-20,057-00 ⁰¹ *KCC ap 10-09-06* (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: Bruce Oil Company KCC License #: 5610
(Owner / Company Name) (Operator's)

Address: 1704 Limestone Road City: McPherson

State: Kansas Zip Code: 67460 Contact Phone: (620) 241 - 2938

Lease: Riordan Well #: 5 Sec. 6 Twp. 15 S. R. 1 East West

c - SW - SW - SW Spot Location / QQQQ County: Dickinson

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: N/A see log Set at: N/A Cemented with: N/A Sacks

Production Casing Size: 4 1/2 Set at: 2661 Cemented with: N/A Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 1320 (G.L. / K.B.) T.D.: 2662 PBTD: _____ Anhydrite Depth: N/A
(Stone Coral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand off bottom to 50 feet above open hole or perforations, put 4 sax cement on sand, rip off and pull casing, set bridge plug at 250 feet, fill hole to surface with cement slurry.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lonny Bruce, Operating Manager

Phone: (620) 241 - 2938

Address: 406 Ponderosa Ct. City / State: McPherson, Kansas 67460

Plugging Contractor: Sunflower Well Service KCC License #: 30280
(Company Name) (Contractor's)

Address: P.O. Box 341, Canton, Kansas 67428 Phone: (620) 628 - 4723

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/31/06 Authorized Operator / Agent: Lonny Bruce
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

BM&S OIL
 BOX 316
 CANTON, KS. 67428
 CONTR KANSAS DRLG. & WELL SERV. CTY DICKINSON

#5 RIARDON "OWWO"

6-15-1E
 SW SW SW

GEOL HARRY HOPKINS FIELD ASH GROVE

E 1320 KB CM 8/13/81 CARD ISSUED 10/15/81 IP P 4 BOPD & WTR
 MISS 2608-2616

+	+
+	+
+	+
+	+

API 15-041-20,057

LOG	TOPS	DEPTH	DATUM
FT R		357	+ 963
B FLOR FT		493	+ 827
WREF		555	+ 765
NEVA		773	+ 547
HOW		1415	- 95
TOP		1510	- 190
HEEB		1780	- 460
TOR		1803	- 483
DOUG		1815	- 495
IATAN		1907	- 587
LANS		1955	- 635
B KC		2325	-1005
CHER		2485	-1165
MISS WAR		2590	-1270
MISS OS		2655	-1335
MISS GC		2765	-1445

OLD INFO: OPERATOR WAS CARTER OIL CO.
 #5 STRAT TEST, SPD 1942, CSG NA,
 COMPLETED AS D&A/ARB

SO IN MISS

NO DST'S

NEW INFO: RE-ENTERED 8/13/81, WSH
 DWN TO MISS, SET 4 1/2" 2661, MICT -
 CO, PF (MISS) 2608-16, SWB GSO,
 NAT, POP, P 4 BOPD & WTR, (GR 35°),
 10/5/81

KIND 2805-1485 SIMP 3340-2020
 HUNT 2953-1633 ARB 3400-2080
 SYL SH 3130-1810 TD 3449-2129
 VIOLA 3230-1910

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED

APR 03 2006

KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bruce Oil Company, L.L.C.
1704 Limestone Rd.
McPherson, KS 67460

April 05, 2006

Re: RIORDAN OWWO #5
API 15-041-20057-00-01
SWSWSW 6-15S-1E, 330 FSL 330 FWL
DICKINSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000