

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Noble Petroleum, Inc.
Address: 3101 N Rock Road, Suite 125 Wichita KS 67226
Phone: (316) 636-5155 Operator License #: 31389
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-12-06 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-039-20980-0000
Lease Name: Votapka
Well Number: 1
Spot Location (QQQQ): _____ - _____ - NW - SW
2050 Feet from North / South Section Line
165 Feet from East / West Section Line
Sec. 15 S. R. 27 East West
County: Decatur
Date Well Completed: 9-13-06
Plugging Commenced: 9-13-06
Plugging Completed: 9-13-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	224'	8 5/8	224'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spotted 25 sx of cement at RTD of 4005', filled hole with rotary mud to 2150' and spotted 25 sx of cement. Filled hole with rotary mud to 1425' and spotted 100 sx of cement. Filled hole with rotary mud to 275' and spotted 40 sx of cement. Filled hole with rotary mud to 275' and spotted 40 sx of cement. Filled hole with rotary mud to 40' and spotted 10 sx of cement to surface. Put 15 sx in the rathole.

Name of Plugging Contractor: Berentz Drilling Company, Inc. License #: 5892

Address: PO Box 782228 Wichita KS 67278-2228

Name of Party Responsible for Plugging Fees: Noble Petroleum, Inc.

State of Kansas County, Sedgwick, ss.

Jay Ablah (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jay Ablah
(Address) 3101 N. Rock Road, Suite 125 Wichita, KS. 67226

SUBSCRIBED and SWORN TO before me this 28th day of September, 20 06

Mari J. Rech My Commission Expires: November 16, 2007
Notary Public

RECEIVED
OCT - 4 2006
KCC WICHITA

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MARI J. RECH
Notary Public - State of Kansas
My Appt. Expires 11-16-07

PPT