

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-20,324 -00-00

LEASE NAME Kendiq "A"

WELL NUMBER 1

2310 ^{NR KCC} Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 4 TWP. 10 RGE. 12W (E) or (W)

COUNTY Osborne

Date Well Completed _____

Plugging Commenced 10-29-96

Plugging Completed 10-31-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg. Russell, KS 67665

PHONE# (913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well oil DH NR KCC

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4215'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	207'	none
				4 1/2	3346'	1550'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3154' & ran 4 sks cement. Shot at 2118', shot didn't go off. While pulling shot out of hole, it went off at 1550'. Pipe came free at 1550'. Pumped 75 sks cement w/200# hulls at 1550'. Pulled pipe to 1125', pumped 30 sks cement w/150# hulls. Pulled pipe 790', pumped 30 sks cement w/150# hulls. Pulled pipe to 250', pumped 80 sks cement & circulated to surface. Pulled rest of pipe. Plugging complete. 60/40 poz 10% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 96

[Signature]
Notary Public

My Commission Expires: _____

