

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-20,306-00-00

LEASE NAME Sigle Trust

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4210 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 2 TWP. 10S RGE. 12 (E) or (W)

COUNTY Osborne

LEASE OPERATOR Russell Oil, Inc.

ADDRESS P.O. Box 272 Russell, Kansas 67665

PHONE# (913) 483-3954 OPERATORS LICENSE NO. 3293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 2-1-96

Plugging Completed 2-6-96

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3434'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	206'	none
				4 1/2"	3429'	2710'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from ___ feet to ___ feet each s Plugged off bottom with sand to 3010 and 4 sacks cement. Shot pipe at 2710'. Pulled up to 1475', Pumped 70 sacks cement with 200# hulls. Pulled to 950', pumped 35 sacks cement with 150# hulls. Pulled to 250', pumped 80 sacks cement with 50# hulls and circulated to surface (60/40 pozmix 10% gel) Pulled rest of casing. Hole stayed full. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc. Russell, Ks. 67665

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 96

[Signature]
Notary Public

My Commission Expires:



RECEIVED
KANSAS CORPORATION COMMISSION
2-12-96
FEB 12 1996

CONSERVATION DIVISION
WICHITA, KS