

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-20,3300000

LEASE NAME Kendig "E"

WELL NUMBER 1

2,970 Ft. from S Section Line

920 Ft. from E Section Line

SEC. 6 TWP. 10 RGE. 12 (E) or (W)

COUNTY Osborne

Date Well Completed 1-20-97

Plugging Commenced 1-26-97

Plugging Completed 1-26-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg, Russell, KS. 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-26-97 (date)

by Ed Schumacher (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3,107'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	221'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Push bridge plug to 920', pump 20 sax cement on plug thru drill pipe. Push bridge plug to 590', pump 80 sax cement on plug thru drill pipe. Push bridge plug to 270', pump 40 sax cement on plug thru drill pipe. Push plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement in rathole and 10 sax cement in mousehole.

Name of Plugging Contractor Shields Oil Producers, Inc. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss. 97

Jack P. Beeman, Sec.-Treas. (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg.
Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1997

Keith Phillips
Notary Public

My Commission Expires:

