

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-141-20,328 <sup>2000</sup>

LEASE NAME Steinle-Yarnell

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Shields Oil Producers, Inc.

SEC. 6 TWP. 10 RGE. 12 XE or (W)

ADDRESS Shields Bldg. Russell, Ks. 67665

COUNTY Russell

PHONE# (913) 483-3141 OPERATORS LICENSE NO. 5184

Date Well Completed \_\_\_\_\_

Character of Well Oil D+A NR KCC

Plugging Commenced 3/4/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3/5/97

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no, new well not yet

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. filed

3350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	209	
				4 1/2	3221	2423'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Sanded back to 3011'. Capped with 4 sks. Shot pipe off at 2423'. Pulled to 1425'. Pumped 70 sks & 2 hulls. Pulled to 950'. Pumped 35 sks & 1 hull. Pulled to 600'. Pumped 35 sks & 1 hull. Pulled to 150'. Circulated cement with 30 sks. Pulled casing, topped off with 20 sks.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 249 E. Beth Drive Sterling, Ks. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, INC.

STATE OF Kansas COUNTY OF Russell

Jack P. Beeman, Sec - Treas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1997

Ruth Phillips  
Notary Public

My Commission Expires:  
USE ONLY ONE SIDE OF EACH FORM

