

4-8

4-061065

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-141-20,332-00-00

NW NE SE /4 SEC. 04, 10 S, 12 W
2310 feet from S section line
990 feet from E section line

Operator license# 5184

Lease Nelson "B" Well # 1

Operator: Shields Oil Producers, Inc.

County: Osborne 107.09

Address: Shields Building
Russell, Kansas 67665

Well total depth 3295 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 227 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Shields Oil Producers, Inc. License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:00 P.M. Day: 8 Month: April Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Oil Producers, Inc. Phone: 913-483-3141

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.
TD in LKC.

APR 15 1997
4-15-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:00 P.M., Day: 8, Month: April, Year: 1997

Actual plugging report:

- 1st. Plug at 1080' w/25 sxs. Anhydrite 1064' - 1094'.
- 2nd. Plug at 800' w/90 sxs. Dakota 535' - 785'.
- 3rd. Plug at 280' w/40 sxs. Surface pipe 227'.
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1985 GL

I did / did not observe the plugging.

Herb Deines
DH
(agent)
Form CP-2/3

INVOICED

APR 16 1997

DATE

INV. NO. 49956

4-8