

9-28

X

4-110028

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-141-20,340-00-00

SW SW NW /4 SEC. 05, 10 S, 12 W
2970 feet from S section line
4950 feet from E section line

Operator license# 5184

Lease: Kendig "D" Well # 1

Operator: Shields Oil Producers, Inc.

County: Osborne 100.75

Address: Shields Building
Russell, Kansas 67665

Well total depth 3100 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Shields Drilling Company License# 5184

Address: 326 Main St. - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 28 Month: September Year: 1997

Plugging proposal received from: Burt Berry

Company: Shields Drilling Company Phone: 913-483-3141

Were: According to KCC rules and regulations.

Plugging Proposal Received by: Roger Moses

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 3:30 A.M., Day: 28, Month: September, Year: 1997

Actual plugging report:

1st. Plug at 920' w/25 sxs. Anhy. 905' - 937'.

2nd. Pug at 630' w/100 sxs. Dakota 332' - 582'.

3rd. Plug at 270' w/40 sxs. Surface Pipe - 217'.

4th. Plug at 40' w/10 sxs.

15 sxs in rathole.

10 sxs in mousehole. 225 total sxs pozmix - 6% gel - 1/4# flocele per sack.

Remarks: Allied Cementing.

Condition of casing (in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug (in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 1782 GL

I did [] / did not [X] observe the plugging.

Roger Moses
(agent)

Form CP-2/3

INVOICED

DATE 10-29-97

INV. NO. 49389

10-29-97
46-688-01