

5-1

4-061070

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-141-20,333-00-00  
230' E. of  
SW SE NE /4 SEC. 05, 10 S, 12 W  
2970 feet from S section line  
760 feet from E section line

Operator license# 5184 Lease Kendig C Well # 1

Operator: Shields Oil Producers, Inc. County: Osborne 105.79

Address: Shields Building Well total depth 3255 feet  
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 213 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well\_\_\_, SWD\_\_\_, D & A X

Plugging contractor: Co Tools License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: 7:45 P.M. Day: 1 Month: May Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Oil Producers, Inc. Phone: 913-483-3141

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floreal per sack.  
Space all plugs with heavy drilling mud through drill pipe.  
RTD in "C" zone of LKC.

KANSAS STATE CORPORATION COMMISSION  
MAY 12 1997  
5-12-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 9:45 P.M., Day: 1, Month: May, Year: 1997

Actual plugging report: \_\_\_\_\_

1st. Plug at 1100' w/25 sxs. Anhydrite 1064' - 1098'.

2nd. Plug at 800' w/100 sxs. Dakota 490' - 790'.

3rd. Plug at 265' w/40 sxs. Surface pipe 213'.

4th. Plug at 40' w/10 sxs.

15 sxs in rathole.

10 sxs in mousehole.


Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO X Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: 1940 GL

I did [ ] did not [ X ] observe the plugging.

  
(agent)  
DH

**INVOICED**  
DATE MAY 13 1997  
INV. NO. 48100