

4-061032

1-6

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-141-20,329 -00-00  
100' W. of  
NW NE NE /4 SEC. 04, 10 S, 12 W  
4950 feet from S section line  
1090 feet from E section line

Operator license# 5184

Lease Nelson Well # 2

Operator: Shields Oil Producers

County: Osborne 103.83

Address: Shields Building  
Russell, Kansas 67665

Well total depth 3195 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Co Tools License# -

Address:

Company to plug at: Hour: 1:00 A.M. Day: 6 Month: January Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Oil Producers Phone: 913-483-3141

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 3:00 A.M. Day: 6 Month: January

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1997  
1-10-97  
CONSERVATION DIVISION  
Wichita, Kansas

Actual plugging report:

1st. Plug at 975' w/25 sxs. Anhydrite 961' - 996'.

2nd. Plug at 685' w/90 sxs. Dakota 435' - 685'.

3rd. Plug at 260' w/40 sxs. Surface pipe 209'.

4th. Plug at 40' w/10 sxs.

15 sxs in rathole.

10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 1885 GL

I did [ ] did not [ X ] observe the plugging.

*[Signature]*  
DH (agent)

Form CP-2/3

INVOICED

DATE JAN 13 1997

INV. NO. 47356

1-6 MAR 14 1997