

3-4

4-070089

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-141-20,341-00-00
210'E.of
NW NE NE /4 SEC. 07, 10 S, 12 W
4950 feet from S section line
780 feet from E section line

Operator license# 6194 Lease: Ringler Well # 1

Operator: ESP Development, Inc. County: Osborne 107.93

Address: 17746 177th Blvd. Well total depth 3321 feet
Paradise, Kansas 67658 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 247 feet

ABAND. oil well, Gas well, Input well, SWD, D&A X

Plugging contractor: VonFeldt Drilling, Inc. License# 9431

Address: P.O. Box 611 - Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 4 Month: March Year: 1998

Plugging proposal received from: Bill Owen

Company: VonFeldt Drilling, Inc. Phone: 785-735-4142

Were: Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack - one 8 5/8 W.P.
Spot plug through drill pipe with heavy drilling mud between all plugs.
8 5/8" set at 247'. No arbuckle cut RTD 3321'.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 3:30 P.M., Day: 4, Month: March, Year: 1998

Actual plugging report: No arbuckle cut.

1st. Plug at 872' w/25 sxs. - Anhydrite 857' - 893'.

2nd. Plug at 600' w/100 sxs. - Dakota Base 300' - 600'.

3rd. Plug at 297' w/40 sxs. - Surface pipe at 247' + 50'.

4th. Plug at 40' w/10 sxs with 8 5/8" wiper plug.

15 sxs in rathole.

10 sxs in mousehole.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 1751 GL

I did [] / did not [X] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE MAR 13 1998

INV. NO. 50053

3-4

3-12-98