

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00666-00-00
Spot: SESENW Sec/Twnshp/Rge: 23-26S-32W
3300 feet from S Section Line, 3140 feet from E Section Line
Lease Name: OHMES Well #: 2
County: FINNEY Total Vertical Depth: 2760 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING, I
Address: PO BOX 818 1200 MAIN STREET
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1100		WITH 2 SX CMT
PROD	5.5	2736	0	WITH 250 SX CMT \$89.70
SURF	8.625	562		WITH 275 SX CMT

Well Type: Gas UIC Docket No: _____ Date/Time to Plug: 09/15/2006 8:30 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: GARY UNRUH Company: KANSAS NATURAL GAS Phone: (785) 625-7353

Proposed Plugging Method: RUN CEMENT BOND LOG FROM 1200' TO TOP ON 5 1/2". SET CAST IRON PLUG AT 1430' APPROX. DUMP (2) SACKS CEMENT ON TOP PLUG W/ BAILOR. LOCATE TOP OF CEMENT BEHIND PRODUCTION PIPE & PERFORATE (4) HOLES IN CASING AT THAT POINT. ATTEMPT TO CIRCULATE CEMENT W/ 80 SACKS OVER CASING CAPACITY TO FILL INSIDE & OUTSIDE OF PRODUCTION PIPE. HOOK ONTO ANNULUS & TRY TO CIRCULATE. CUT WELL OFF 6' BELOW GROUND, WELD CAP & BACKFILL TO COMPLETE. KCC - MR. JIM HOLLAND.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2006 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TUBING & RODS STUCK IN HOLE. TOP OF FISH @ 1400'. CIBP @ 1100' WITH 2 SX CMT. RAN BOND LOG. TOC @ 900'. PERFORATE AT 785'. PUMP 210 SX CMT, CIRCULATED CMT TO SURFACE. CASING STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
2700	2718		KRIDER
2678	2696		HERRINGTON

INVOICED
DATE 10/6/06
WEL. NO. 2007060646

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

Plugged through: CSG

District: 01



Signed

[Signature]

(TECHNICIAN)

RECEIVED
OCT - 5 2006
KCC WICHITA

Form CP 1/3

[Handwritten initials]