

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-049-21959-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 16-31S-10E  
2310 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: WALKER JOE Well #: 2  
County: ELK Total Vertical Depth: 2069 feet

Operator License No.: 3359  
Op Name: T & R OIL COMPANY, A GENERAL PAR  
Address: PO BOX 92  
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2069	0	

\$ 67.24

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2006 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/28/2006 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" TUBING INSIDE 4.5" CASING DOWN TO 2000' & PUMPED GEL AND 10 SACKS CEMENT FOR BOTTOM PLUG & GEL SPACER. PULLED 1" OUT & PERFORATED 4.5" CASING @ 500'. RAN 1" BACK IN TO 500' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 65 SACKS CEMENT & 4 SACKS GEL.

Perfs:

RECEIVED  
KCC DISTRICT #3

AUG 8 2006 RE

CHANUTE, KS


INVOICED  
DATE 10/5/06  
NO. 2007060636

Remarks: PLUGGED DEPLETED OIL WELL.

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

RECEIVED  
OCT - 2 2006  
KCC WICHITA

Form CP-2/3

PLT